

# BID PROPOSAL

Client: Town of Bluffton

Proj. Name: Buck Island - Simmonsville Sewer Extension  
(Phase 3)

Date:

Item #	Description	Estim. Qty.		Unit Price	Total Price
General					
1	Clearing and Grubbing, incl. street R/W, easements & other areas as shown on the plans	1	LS		
2	Grading and Project Miscellaneous shall include all grading, including off-site removal and replacement of unsuitable material, to meet the finished grades shown on the plans, and project staking, testing, insurance, bonds & all miscellaneous items not included elsewhere in this bid schedule to complete the project in accord with the plans and specifications	1	LS		
3	Rem. and Rep. Standard Asphalt Paving Section	433	SY		
4	Rem. and Rep. Asphalt Paving (SCDOT Section)	35	SY		
5	Mill and Replace Existing SCDOT Paving	450	SY		
6	Remove and Replace Concrete Paving Section	45	SY		
7	Silt Fence - Type "A"	4,425	LF		
8	Tree Protection (As Directed by Owner)	5,000	LF		
9	Grassing	17,500	SY		

**SUBTOTAL**

<b>SANITARY SEWER SYSTEM</b>					
1	4" PVC Service Lat. (Direct Bury)	500	LF		
2	6" PVC Service Lat. (Direct Bury)	390	LF		
3	6" PVC Service Lat. (Horizontal Directional Drill)	300	LF		
4	8"x4" Service Wye	11	EA		
5	8"x6" Service Wye	18	EA		
6	4" Cleanout For Future Connection	55	EA		
7	8" PVC Sewer Pipe 0' - 6'	550	LF		
8	8" PVC Sewer Pipe 6' - 8'	1,050	LF		
9	8" PVC Sewer Pipe 8' - 10'	650	LF		
10	8" PVC Sewer Pipe 10'-12'	250	LF		
11	8" PVC Sewer Pipe 12' - 14'	485	LF		

12	10" PVC Sewer Pipe 14' - 16'	475	LF		
13	Jack and Bore 20" Steel Casing W/Carrier Pipe	600	LF		
14	Standard Manhole 0' - 6'	2	EA		
15	Standard Manhole 6' - 8'	4	EA		
16	Standard Manhole 8' - 10'	4	EA		
17	Standard Manhole 12' - 14'	3	EA		
18	Standard Manhole 14' - 16'	4	EA		
19	Core Drill Existing Manhole	1	EA		

**SUBTOTAL**

<b>SANITARY SEWER SYSTEM - NON DEV</b>					
1	4" PVC Service Lat. (Direct Bury)	85	LF		
2	6" PVC Service Lat. (Direct Bury)	65	LF		
3	6" PVC Service Lat. (Horizontal Directional Drill)	25	LF		
4	8"x4" Service Wye	3	EA		
5	8"x6" Service Wye	5	EA		
6	4" Cleanout For Future Connection	15	EA		

**SUBTOTAL**

<b>WATER DISTRIBUTION SYSTEM</b>					
1	1" Service Lateral (Direct Bury)	245	LF		
2	1" Service Lateral (HDD)	80	LF		
3	1" Corporation Stop	13	EA		
4	1" Curb Stop	13	EA		
5	2" Manifold Assembly	1	EA		
6	Fire Hydrant w/6" Valve & Box	1	EA		
7	6" Water main (incl. fittings & thrust restraints)	380	LF		
8	Connect to Existing Water main	2	EA		

**SUBTOTAL**

<b>ADD ALTERNATE No. 1</b>					
1	4" PVC Service Lat. (Direct Bury)	7,000	LF		
2	4" Cleanout	150	EA		
3	Abandon Septic Tanks	45	EA		

4	1" Service Lateral (Water)	3,000	LF		
5	House Connection (Water)	15	EA		
6	Site Protection and Restoration	1	LS		

SUBTOTAL

GENERAL

SANITARY SEWER SYSTEM

SANITARY SEWER SYSTEM - NON DEV

WATER DISTRIBUTION SYSTEM

BASE BID

ADD ALTERNATE No. 1

BASE BID + ADD ALTERNATES